

Town of East Lyme

P.O. DRAWER 519



NIANTIC, CONNECTICUT 06357

Town Engineer
William A. Scheer PE LS

860-691-4101
FAX 860-739-6930

POST AND RAIL REPLACEMENT NIANTIC RIVER / ROUTE 156 BOARDWALK

August 2, 2011

Addendum No. 2

1. Page 4, Item #19 – Bid Instructions and General Conditions

Remove: September 6, 2011 Contract Signing / Notice to Proceed / Begin Construction

Add: August 10, 2011 Contract Signing / Notice to Proceed / Begin Construction

2. Page 7 – Notice to Contractor, Permits

Add: At end of second paragraph, “Contractor shall complete CT DOT *Permit Bond* and *Certificate of Insurance* forms for submission to DOT (DOT Instructions and Forms have been included as an attachment).”

3. Page 8 – Project Clarifications

Add: 8) The contractor may consider modifying existing rail panel sections for shorter horizontal (two panels anticipated) rail panels that need to be fabricated at the end of the boardwalk. The angled panels shall be custom fabricated per plans and specs.

Add: 9) Existing 2x4 composite rail cap lengths slightly differ; contractor shall install rail caps flush with posts.

Add: 10) The contractor may consider connecting proposed posts to the existing concrete barrier or other suitable connection methods at the west end of the boardwalk. Contractor shall provide the Town Engineering Department with suitable shop drawing & detail prior to construction.

Add: 11) Contractor to provide fender washer of comparable size in place of existing washer for post installations; do not use large existing washer.

Add: 12) 4x4x1/4 Galv. angles and (short) 5/8” bolts called for as “from the Niantic Bay Boardwalk” will not be provided by the Town. Instead, #8 or larger galv. or stainless steel screws with 2” min. embedment into new brace blocks must be used to anchor the new 2x10 rail brace blocks to the existing 2x10’s. Additionally, the 3/8” bolts and hardware needed to anchor rail panels to the posts will be provided by the Contractor. Any new miscellaneous hardware (i.e. bolts, nuts, and circular washers) shall conform to ConnDOT 816 Section M.06.02 (Metals: Structural Steel & Other Structural Materials), Item 5. High Strength Bolts.

4. Page 10, Item# 11416005A – Wire Cloth Rail Panel, Materials

Add: Custom rail panels shall be hot dipped galvanized and color galvanized “gray” to match color of existing rail panels. Color sample shall be provided for approval.

5. Page 12, Item# 0913068 – Temporary Construction Safety Fence

Remove: 6’ Chain Link Fence

Add: Orange construction fence in front of wood framing to create a physical barrier.

END ADDENDUM NO. 2

**THIS ADDENDUM DOES NOT NEED TO BE ATTACHED TO THE
SUBMITTED BID PACKAGE**