



#### PROPOSED PLANT MATERIAL:

| Quant.  | Botanical/Common                          | size           | mature |
|---------|-------------------------------------------|----------------|--------|
| TREES:  |                                           |                |        |
| 9       | Amelanchier Canadensis / Shadblow         | 6'-8' ms       | 20'    |
| 7       | Acer Rubrum "Karpick" / Red Maple         | 4"-cal         | 45'    |
| 1       | Cornus Mas / Yellow Dogwood               | 6'-8' ms       | 15'    |
| 6       | Gleditsia Triacanthos / Honeylocust       | 3"-cal         | 40'    |
| 30      | Juniperus Virginiana / Red Cedar          | 6'-8"          | 25'    |
| 6       | Prunus "Okame" / Upright Cherry           | 2 1/2"-3" cal. | 25'    |
| SHRUBS: |                                           |                |        |
| 36      | Clethra Alnifolia Compacta                | 3 gal.         | 4'     |
| 36      | Ilex Crenata Compacta / Compact Holly     | 3 gal.         | 3'     |
| 48      | Ilex Aquifolium "Winnifred"               | 3 gal.         | 3'     |
| 175     | Juniperus "Sargent's Windii" Juniper      | 2 gal.         | 15"    |
| 5       | Juniperus Chinensis / Robusta Juniper     | 6"-8" b&b      | 10'    |
| 1300    | Liriope Spicata / Creeping Lily Turf      | 4" poi         | 6"     |
| 18      | Pennisetum Alopecuroides / fountain grass | 2 gal.         | 18"    |
| 24      | Taxus Baccata / Low Grow Taxus            | 15"            | 2'     |
| 24      | Viburnum Dentatum / Arrowwood Vib.        | 7 gal.         | 8'     |

#### NOTES:

All material to be field determined by TEC.  
 All planting areas to receive 2" of mulch after planting.  
 Prior to start, contractor shall thoroughly review the drawing and project site and familiarize himself with all existing conditions and features.  
 Contractor to maintain any erosion control and sediment control that has been laid out until all disturbed areas have been seeded or have had wood chips or mulch applied.  
 All invasive plant material to be removed from project site.

This plan is for graphic representation of the landscape only. While they express the scope and intent of the project, they are not to be used as construction documents.  
 Refer to civil and site drawings for all information regarding clearing limits, drainage, and exact location of roads and driveways and specific dimensions of all proposed building.

## 138 BPR

EAST LYME, CONNECTICUT

LANDSCAPE PLAN LP-1  
 TEC LANDSCAPE DESIGN, INC.  
 JOHN W. CUNNINGHAM  
 62 WALL STREET  
 MADISON, CONNECTICUT  
 203.245.4295  
 JOHN@TECLANDSCAPE.COM  
 SCALE: 1"= 20'  
 PROJECT: 5043  
 DATE: 5-12-2022  
 REVISED:



NOTES: All final elevations and dimensions of planting areas will be outlined for contractor prior to commencement.  
 All planting area boundaries and elevations to be field determined.  
 All plant material will be selected by and field determined by TEC.  
 Please refer to engineer's plan for all final elevations and layout of all proposed construction.

This plan is for graphic representation of the landscape only.  
 Refer to civil and site drawings for all information regarding clearing limits, drainage, exact location of walkways, driveways and proposed construction.

