

ZONING DATA TABLE			
EAST LYME RESIDENCE 'RU-40/20' D			
REQUIRED	EXISTING		
40,000 S.F.	751,410± S.F. (17.25 AC.) (GROSS) 320,090± S.F. (7.35 AC.) (NET) (1) (3)		
150 FT.	451± FT. (1)		
40 FT.	388.7± FT. (EX. DECK)		
20 FT.	318.6± FT. (EX. DECK)		
20 FT.	30.4± FT. (EX. DECK) 46.4± FT. (EX. BUILDING)		
30 FT.	UNKNOWN		
20% (±237,402 S.F.)	±3.4% (39,910± S.F.)		
	AST LYME R REQUIRED 40,000 S.F. 150 FT. 40 FT. 20 FT. 20 FT. 30 FT. 20%		

SYMBOL	QUANTITY	COMMON NAME	BOTANICAL NAME	SIZE (AT MATURITY)
A CONTRACT OF A	7	HIGHBUSH BLUEBERRY	VACCINIUM CORYMBOSUM	6' (DIAMETER) 4'—6' (HEIGHT)
	7	CLETHRA	CLETHRA ALNIFOLIA	5'-6' (DIAMETER) 4' (HEIGHT)
影	6	LANCE-LEAF COREOPSIS	COREOPSIS LANCEOLATE	1'-1.5' (DIAMETER) 1'-2' (HEIGHT)
H	6	BUTTERFLY MILKWEED	ASCLEPIAS TUBEROSA	1'-2' (DIAMETER) 2'-3' (HEIGHT)
*	7	TUFTED HAIRGRASS	DESCHAMPSIA CESPITOSA	1'-2' (DIAMETER) 1'-3' (HEIGHT)

### DEEP TEST PIT DATA DATE: 2/9/24

WITNESSED BY: JOE WREN, P.E. (INDIGO) JOSEPH BLANCHARD, REHS/R.S (LEDGE LIGHT HEALTH DISTRICT) EXCAVATED BY: SPENCER BEERS

### TP #1

TOPSOIL & ORGANIC MATTER

-2.3''TAN GRAY FINE SAND WITH ROOTS

23-72

ORANGE BROWN MEDIUM SAND 72-88'

ORANGE BROWN MEDIUM-COARSE SAND WITH SOME GRAVEL & COBBLES (SATURATED) NO MOTTLING

GROUNDWATER @ 68" NO LEDGE

### TP #2

TOPSOIL & ORGANIC MATTER

3-18" GRAY TAN VERY FINE SAND

18 - 30"DARK GRAY VERY FINE SAND WITH ROOTS

30 - 64'ORANGE BROWN FINE-MEDIUM SAND

64 - 90"ORANGE BROWN MEDIUM-COARSE SAND WITH SOME GRAVEL & COBBLES (SATURATED)

MOTTLING @ 75" GROUNDWATER @ 71"

NO LEDGE

### PERCOLATION TEST DATA CONDUCTED BY: CAROLINE O'HAGAN (INDIGO)

PERC	А
DATE:	2/16/24

2///2/ 2/	
DEPTH: 30	3"±

TIME (MIN.)		DEPTH (INCHES)	DROP (INCHES)	PERC RA (MIN./IN)
0	0	24		
1	0	26 1/4	2 1/4	0.4
2	0	28 3/4	2 1/2	0.4
3	0	30	1 1/4	0.8
4	0	32 1/4	2 1/4	0.4
5	0	34	1 3/4	0.6

PERC RATE = FASTER THAN 1.0 MIN./INCH


(DRY)


## <u>GENERAL NOTES (SEPTIC SYSTEM)</u>:

- DOWNGRADIENT GROUNDWATER DRAIN.
- TO CONSTRUCTION.

### <u>GENERAL CONSTRUCTION NOTES (SEPTIC SYSTEM):</u>


- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CURRENT CONNECTICUT PUBLIC HEALTH CODE, AS AMENDED. 2. A LICENSED SURVEYOR SHALL FIELD STAKE THE SEPTIC SYSTEM PRIOR TO CONSTRUCTION.
- 3. NO WORK SHALL COMMENCE IN THE SYSTEM AREA UNTIL A SEPTIC PERMIT HAS BEEN TAKEN OUT BY THE LICENSED INSTALLER.
- ENGINEER PRIOR TO CONSTRUCTION. ALL MODIFICATIONS MUST BE APPROVED BY THE ENGINEER AND TOWN SANITARIAN PRIOR TO CONSTRUCTION.
- THE ENGINEER AND SANITARIAN.
- FROM OVER COMPACTION AND SILTATION ONCE EXPOSED.
- WITHOUT THE APPROVAL OF THE SANITARIAN.
- MANHOLES AND LEACHING SYSTEM ENDS. THE AS-BUILT PLAN SHALL BE COMPLETED IN A TIMELY MANNER.
- 11. NO HEAVY EQUIPMENT SHALL BE DRIVEN OVER THE INSTALLED LEACHING SYSTEM AREA.
- 13. THE LICENSED INSTALLER IS RESPONSIBLE TO INSTALL THE SUBSURFACE SEWAGE DISPOSAL SYSTEM IN ACCORDANCE WITH THE APPROVED PLAN.
- WWW.GEOMATRIXSYSTEMS.COM.
- LEAKS TO THE SATISFACTION OF THE ENGINEER AND THE TOWN SANITARIAN. 17. THE LICENSED INSTALLER SHALL CONFIRM THAT NO LEDGE IS PRESENT WITHIN 48 INCHES BELOW THE BOTTOM OF THE PROPOSED LEACHING SYSTEM.
- IN PONDING ON THE SUBJECT PROPERTY OR ANY ADJACENT PROPERTY OR ROADWAY.
- 19. THE LICENSED INSTALLER SHALL INCLUDE ALL ADEQUATE PROVISIONS FOR FREEZE PROTECTION FOR ALL PIPING AND JUNCTIONS. 20. LICENSED INSTALLER SHALL PROVIDE SIEVE ANALYSES FOR C-33 SAND PRIOR TO CONSTRUCTION.






THE LICENSED INSTALLER SHALL CONFIRM THAT THE SELECTED SEPTIC TANK SHALL BE CONSISTENT WITH THE DIMENSIONS INCLUDED ON THE PLAN AND SHALL MEET ALL CT PUBLIC HEALTH CODE REQUIREMENTS. IF TANK DIMENSIONS DO NOT MATCH THOSE INCLUDED ON THE APPROVED PLAN, THE INSTALLER SHALL REVIEW WITH THE DESIGN ENGINEER PRIOR TO ORDERING THE TANK. 1.000-GALLON CONCRETE SEPTIC TANK DETAIL


NOT TO SCALE






		<u>57</u>	<u>\  \ </u>
DESIGN PERCOLATION RATE	BUILDING TYPE	REQUIRED LEACHING AREA	
LESS THAN 1.0 MIN./INCH	NON-RESIDENTIAL NON-PROBLEMATIC	402 S.F. (1)	30 GST

STRUCTURE	BUILDING TO SEPTIC TANK	SEPTIC TANK	LEACHIN
INV. IN (FT.)		6.50	5.7
INV. OUT (FT.)	7.25	6.25	
	A MIN OF 12" OF CO		





# DEP BULLETIN 34.

## PROJECT DESCRIPTION

THE APPLICANT IS PROPOSING TO DEMOLISH THE EXISTING BEACH CABANAS & REMOVE A PORTION OF THE EXISTING PAVED PARKING AREA, CONSTRUCT NEW BEACH CABANAS AND DECKS, INSTALL A NEW 100% CONNECTICUT PUBLIC HEALTH CODE-COMPLIANT SEPTIC SYSTEM AS WELL AS OTHER ASSOCIATED IMPROVEMENTS. THE PROPOSED STRUCTURE WILL BE CONSTRUCTED ON A PILE SUPPORTED FOUNDATION AND WILL NOT HAVE FOOTING DRAINS. THE STRUCTURE IS PROPOSED TO BE IN COMPLIANCE WITH FEMA REGULATIONS AND LOCAL FLOOD ORDINANCES EFFECTIVE 2/6/2013.

CONSTRUCTION IS ANTICIPATED TO COMMENCE IN FALL 2024. ALL EROSION AND SEDIMENT CONTROLS SHALL BE INSTALLED PRIOR TO CONSTRUCTION ACTIVITIES. E & S CONTROLS SHALL BE MAINTAINED AND REPAIRED OR REPLACED AS NEEDED THROUGHOUT THE CONSTRUCTION DURATION. ALL E & S CONTROLS SHALL BE REMOVED AND PROPERLY DISPOSED OF AS SOON AS THE SITE IS COMPLETELY STABILIZED.

### CONSTRUCTION SEQUENCE

- 1. CONTACT "CALL BEFORE YOU DIG" TO MARK OUT ALL UTILITY LOCATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES. 2. ENSURE ALL LAND USE PERMITS HAVE BEEN SECURED. OBTAIN ALL NECESSARY PERMITS.
- 3. A LICENSED LAND SURVEYOR SHALL STAKE OUT ALL PROPOSED IMPROVEMENTS PRIOR TO ANY CONSTRUCTION.
- 4. INSTALL ALL EROSION AND SEDIMENT CONTROLS.
- 5. CLEAR TREES/BRUSH AND REMOVE STUMPS NECESSARY FOR CONSTRUCTION AND GRADING. 6. DEMOLISH EXISTING CABANAS AND DECKING.
- 7. BEGIN CONSTRUCTION OF PROPOSED CABANAS.
- 8. INSTALL SEPTIC SYSTEM AND UNDERGROUND UTILITIES.
- 9. CONNECT ALL UTILITIES TO THE CABANAS.
- 10. FINISH GRADE AND PAVE PORTION OF DRIVEWAY. SAW-CUT & REMOVE EXISTING PORTION PARKING LOT AS SHOWN. 11. FINISH GRADE, SEED, MULCH AND LANDSCAPE ALL DISTURBED AREAS AS REQUIRED. INSTALL LANDSCAPE BUFFER SHRUBS.
- 12. REMOVE ALL EROSION AND SEDIMENT CONTROLS ONCE SITE IS COMPLETELY STABILIZED. DISPOSE OF PROPERLY.

### LAND DISTURBANCE

1. ALL EXISTING VEGETATION OUTSIDE OF THE CLEARING LIMITS SHALL BE PROTECTED. EXISTING VEGETATION SHALL BE REMOVED ONLY IN AREAS NECESSARY FOR SITE CONSTRUCTION ACTIVITIES. ANY ADDITIONAL CLEARING OUTSIDE OF THE PROPOSED CLEARING LIMITS SHALL BE APPROVED BY TOWN STAFF PRIOR TO CLEARING.

- 2. ALL AREAS SHALL REMAIN UNDISTURBED UNTIL IMMEDIATELY PRIOR TO SITE DEVELOPMENT.
- 3. ALL CONSTRUCTION EQUIPMENT, MATERIALS AND STOCKPILES SHALL NOT BE PLACED OUTSIDE OF THE DISTURBED AREAS. 4. ALL TREES, BRUSH, STUMPS, WOOD CHIPS OR OTHER ORGANIC MATTER SHALL BE DISPOSED OF PROPERLY OFF-SITE. WOOD CHIPS MAY BE USED AS A SILTATION BARRIER DURING CONSTRUCTION AND SPREAD AFTER SITE IS STABILIZED. NO ORGANIC MATTER INCLUDING TREES, BRUSH AND STUMPS SHALL BE BURIED ON-SITE.

## STRIPPING AND STOCKPILING

ALL STOCKPILES THAT CONSIST OF ERODIBLE MATERIALS SHALL BE LOCATED WITHIN AREAS AS SHOWN ON THE SITE PLAN AND SURROUNDED BY A SILTATION BARRIER. ANY STOCKPILE THAT WILL REMAIN UNDISTURBED FOR A PERIOD LONGER THAN 30 DAYS SHALL BE SEEDED WITH A TEMPORARY GRASS SEED MIXTURE TO PREVENT EXCESSIVE EROSION AND SEDIMENTATION.

TRENCH EXCAVATION AND BACKFILL THE CONTRACTOR SHALL PROPERLY MAINTAIN ALL BACKFILLED EXCAVATIONS. ANY DEPRESSIONS DUE TO SETTLING IN THESE AREAS SHALL BE FILLED AND RESEEDED AS NECESSARY. THE WIDTH OF ALL EXCAVATED TRENCHES SHALL BE KEPT AS NARROW AS PRACTICABLE TO ACCOMMODATE THE WORK. ALL MATERIALS EXCAVATED FROM TRENCHES SHALL BE STOCKPILED AND USED AS TRENCH BACKFILL MATERIAL UNLESS IT IS DETERMINED TO BE UNSUITABLE BY THE ENGINEER. EXCESS MATERIALS SHALL BE PROPERLY DISPOSED OF BY THE CONTRACTOR.

### SOIL EROSION AND SEDIMENT CONTROLS

ALL ADJACENT PROPERTIES AND RECEIVING WATERCOURSES AND/OR WETLAND AREAS SHALL BE ADEQUATELY PROTECTED FROM SOIL EROSION AND SEDIMENTATION BOTH DURING AND AFTER CONSTRUCTION. ADDITIONAL EROSION AND SEDIMENT CONTROLS MAY BE REQUIRED BY THE TOWN AND SHALL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSTALLATION AND MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROLS BEFORE, DURING AND AFTER CONSTRUCTION. THE CONTRACTOR IS ALSO RESPONSIBLE FOR THE PROPER REMOVAL AND DISPOSAL OF ALL EROSION AND SEDIMENT CONTROLS ONCE THE SITE IS COMPLETELY STABILIZED. ALL EROSION AND SEDIMENT CONTROLS SHALL BE INSPECTED WEEKLY AND AFTER ALL RAINFALL EVENTS. E & S CONTROLS SHALL BE REPAIRED OR REPLACED AS NECESSARY WITHIN 24 HOURS THROUGHOUT THE CONSTRUCTION DURATION.

ALL ACCUMULATED SEDIMENTS AT ALL EROSION AND SEDIMENT CONTROLS SHALL BE PERIODICALLY REMOVED AND SPREAD IN AREAS THAT ARE NOT SUBJECT TO EROSION. THE CONTRACTOR SHALL EMPLOY BEST MANAGEMENT PRACTICES TO CONTROL STORWWATER DISCHARGES AND TO PREVENT EROSION AND SEDIMENTATION AND TO OTHERWISE PREVENT POLLUTION OF PRIVATE PROPERTY. THE CONTRACTOR SHALL IMMEDIATELY INFORM THE TOWN OF ANY PROBLEMS INVOLVING EROSION AND/OR SEDIMENTATION THAT HAVE DEVELOPED IN

THE COURSE OF, OR THAT ARE CAUSED BY, THE AUTHORIZED WORK. THE RESPONSIBLE CONTACT PERSON FOR THE INSTALLATION AND MAINTENANCE OR EROSION AND SEDIMENTATION CONTROLS ON THIS PROJECT WILL BE THE SITE CONTRACTOR AND / OR THE GENERAL CONTRACTOR. ONCE THE GENERAL CONTRACTOR IS SELECTED, CONTACT INFORMATION WILL BE PROVIDED TO THE TOWN.

### VEGETATIVE TURF ESTABLISHMENT PROCEDURE

SCARIFY ALL AREAS TO BE TOPSOILED AND SEEDED. APPLY A MINIMUM OF 4 INCHES OF TOPSOIL ON ALL AREAS TO BE SEEDED. APPLY GRASS SEED, LIME, FERTILIZER AND MULCH ACCORDING TO THE FOLLOWING SCHEDULE: PERMANENT SEED MIXTURE:

CREEPING RED FESCUE REDTOP TALL FESCUE TOTAL

0.45 LBS. PER 1,000 SQ. FT. 0.45 0.95


FERTILIZER: 10-10-10 APPLY AT 7.5 LBS. PER 1,000 SQ. FT.

*LIMESTONE* APPLY AT 150 LBS. PER 1,000 SQ. FT.

MULCHING: SPREAD HAY OR STRAW OVER ALL AREAS AFTER SEEDING. USE 1 1/2 TO 2 BALES PER 1,000 SQ. FT. TARGET FOR 100% COVERAGE. ANCHOR BY USING NETTING OR TRACKING AS NECESSARY. TEMPORARY EROSION CONTROL BLANKETS:

USE TEMPORARY EROSION CONTROL BLANKETS ON ALL SEEDED SLOPES EQUAL TO OR STEEPER THAN 3(H):1(V) IN STRICT CONFORMANCE WITH THE MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS. SEEDING DATES


SEEDING DATES IN CONNECTICUT ARE NORMALLY APRIL 1 THROUGH JUNE 15 AND AUGUST 15 THROUGH OCTOBER 1. SEED GERMINATION NORMALLY CANNOT BE EXPECTED FROM NOVEMBER THROUGH FEBRUARY. IF ADEQUATE SEED GERMINATION IS NOT POSSIBLE DUE TO TIME OF YEAR CONSTRAINTS, MULCHING SHALL BE ADEQUATELY PROVIDED TO PROTECT THE SEED FROM WIND AND SURFACE EROSION UNTIL THE WEATHER IMPROVES AND THE SEEDING BECOMES WELL ESTABLISHED.



2"x2"x4'-0" STAKE: ANGLE

HANDICAPPED PARKING STALL DETAIL

NOT TO SCALE



- DEVICE.
- (MARV) FOR THE FOLLOWING:

PUNCTURE

- FLOW RATE PERMITTIVITY (SEC<sup>-1</sup>)
- UV RESISTANCE
- DISPLACED.
- ENCOUNTERED.

